

8-15-18W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H. C. BENNETT
Farm - Swires No. 2.

SEC. 8 T. 15 R. 18W
NE NW SW

Total Depth. 3584'
Comm. 6-20-45 Comp. 7-12-45
Shot or Treated.
Contractor.
Issued. 1-19-46

County. Ellis
KANSAS



Elevation. 1994 ft

Production. Pot. 25 Bbls.

CASING:

13 3/8"	127'	Cem.
8 5/8"	1160'	Cem.
5 1/2"	3577'	Cem.

Figures Indicate Bottom of Formations.

gravel, sand & shale	90
shale, shells, & iron	135 ✓
shale, & shells	200
shale, lime, shells	345
sand & shale	385
sand pyrite	420 ✓
sand & shale	475
sand, shale pyrite	585 ✓
sand, pyrite shale	650 ✓
sand	810
sand, red bed	840
red rock & sand	830
red bed & pyrite	1085 ✓
red rock & pyrite	1156 ✓
anhydrite	1205
shale	1250
shale & shells	1575
salt & shale	1800
shale & shells	1870
shale & lime	2180
lime	2280
lime & shale	2690
shale & shells	2775
shale & lime	2945
shale & shells	2970
lime & shale	3137
lime	3230
shale & lime	3250
lime	3560
conglomerate	3575
lime	3584
Total Depth	