

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

8-15-18W
Plotted Texas CO.

GULF OIL CORP.
James A. Swires No. 2.

SEC.8 T.15 R.18W
NE SE SW

Total Depth. 3563'
Comm. 6-3-36 Comp. 8-12-36
Shot or Treated. 1000 & 1000 Gals.
Contractor.
Issued. 9-12-36

County. Ellis

SEP 12 1936



CASING:

15 $\frac{1}{2}$ "	107'	Left in.
10 $\frac{3}{4}$ "	1099'	" "
7"	3223'	" "
5 $\frac{1}{2}$ "	3554'	" "

Elevation.

Production. Pot. 1160 B.
No water.

Figures Indicate Bottom of Formations.

surface clay	20	shale	2720	red rock	3522
lime shells	50	lime	2730	lime	3554
sdv shale	108	shale & shells	2801	lime Siliceous	3563
shells	118	shale hrd & shells	2843	Total Depth	
shale & shells	274	Topeka lime brkn	2858		
shells	294	Topeka lime	2972		
shale	350	lime	3010		
shale & shells	503	shale	3025		
sand	512	lime	3032		
sticky shale	550	lime brkn	3045	ACIDIZED:	
shale & shells	605	shale	3065	7- 1-36	with 1000 gallons.
sandy red beds	660	lime brkn	3100	8-11-36	with 1000 gallons.
sand	825	lime hrd	3140		
red rock	885	lime	3175		
sticky shale	995	shale	3180		
shale	1075	lime	3226	Siliceous lime 3554-3563'	
iron & lime	1100	shale	3233		
shale & red rock	1353	lime	3243		
shale	1400	shale red	3251		
shale & shells	1432	lime Oswald	3261		
shale	1564	shale light	3265		
salt brkn	1618	shale dark	3269		
salt & shells	1740	lime	3303		
shale	1865	lime hrd	3321		
lime grey sft	1895	lime	3328		
shale & brkn lime	1969	lime grey	3335		
shale	1995	lime brkn	3347		
lime	2000	lime	3352		
shale	2010	lime brkn	3357		
sdv grey lime	2050	lime	3391		
lime brkn	2090	lime hrd	3394		
shale	2135	shale	3396		
lime hrd	2367	lime	3415		
shale	2395	shale blue	3420		
lime	2403	lime	3460		
shale	2425	lime white	3465		
shale & lime shells	2489	lime	3492		
shale-brkn lime	2560	lime white	3500		
lime brkn	2578	lime	3510		
shale	2598	red shale into brown			
shale & shells	2699	slate	3515		