


KANSAS GEOLOGICAL SOCIETY
501 East Murdock
Topeka, Kansas

MAY 15 1971



14-15-2W
SE SW NW

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

May 3, 1971

COMPANY: GEORGE R. HESS & LARRY MOORE RANCH, INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: MELANDER # 3
 LOCATION: SE SW NW, Sec. 14-15-2W
 Saline County, Kansas
 COMMENCED: April 27, 1971
 COMPLETED: May 2, 1971
 ELEVATION: 1365 K. B.

Dry/miss

0	to	790	Shale & Lime
790	to	1065	Lime & Shale
1065	to	1790	Shale & Lime
1790	to	2585	Lime
2585	to	2817	Lime & Shale
2817	to	2824	Burgess Sand
2824	to	2837	Mississippi
		2837	T. D.

Cut 12 1/4 in. hole to 129 ft. and run 131 ft. of 8 3/8 in. surface pipe, cemented with 90 sacks of cement at 129 ft. Plug down at 11:00 A. M., April 28, 1971. Cut 7 7/8 in. hole to 2837 ft. Hole dry and abandoned. Filled with mud to 125 ft. Set plug & put in 25 sacks of cement. Filled with mud to 40 ft. & set plug. Put in 10 sacks of cement, 2 sacks in rathole. Plugging completed at 7:00 P. M., May 2, 1971. Plugging completed by State Plugger, Gilbert Toman, Holyrood, Kansas.

TOPS: LANSING - 2182' BURGESS SAND - 2817' MISSISSIPPI - 2824'

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your MELANDER #3, located on the SE SW NW, Sec. 14-15-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 3rd day of May, 1971.