

7-15-2W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SOLAR OIL CO.
Farm- Dieter

No. 1

SEC. 7 T. 15 R. 2W
C E/2 SW NE

Total Depth. 3225'

Comm. 10-1-60


Comp. 10-11-60

Shot or Treated.

Contractor. Harms-Burt Drlg.

Issued. 1-7-61

County Saline
KANSAS



CASING:

13 3/8" 80' cem w/75 sx.
8 5/8" 340' cem w/200 sx.
5 1/2" 3219' cem w/75 sx.

Elevation. 1252' KB

Production. State Pot. 192 bbls
oil, 50% wtr, 24 hr

Figures indicate Bottom of Formations.

sand	65
shale	132
lime	332
anhydrite	340
lime & shale	925
shale & lime	1935
lime & shale	2030
lime	2342
lime & shale	2665
Mississippi	2950
shale	3058
lime	3225
Total Depth	

TOPS:

Anhydrite	332
Lansing-Kansas City	2030
Mississippi	2661
Kinderhook	2934
Hunton	3058
Maquoketa	3136
Maquoketa Dolomite	3218

Acidized - 1000 gallons
Frac'd w/40,000# sand and 40,000 gal water

DST #1 3219-3225', op 2 hrs, shut in 20
mins, rec. 35' oil cut mud, IBHP 1155#,
FBHP 965#.