

11-15-2W

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**


COMPANY **CLOUD DRILLERS**

SEC. 11 T. 15 N. 2W  
 LOC. E $\frac{1}{2}$  NW SW

FARM **Kruger** NO. 1

COUNTY **Saline**

TOTAL DEPTH **2795'**  
 COMM. **6-20-68** COMP. **6-24-68**  
 SHOT OR TREATED  
 CONTRACTOR **Blackstone Drilling**  
 ISSUED **10-12-68**



CASING

20	10	
15	8 5/8" 108'	cem w/ 80 sx
12	6	
13	5	

ELEVATION **1323' KB**  
 PRODUCTION **DRY/MISS**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	30	Clay
30	to	60	Lime
60	to	105	Blue Shale
105	to	310	Lime & Shale
310	to	725	Shale & Lime
725	to	1010	Lime & Shale
1010	to	1475	Shale & Lime
1475	to	1757	Lime & Shale
1757	to	1975	Lime
1975	to	2131	Shale & Lime
2131	to	2650	Kansas City
2650	to	2787	Shale & Lime
2787	to	2795	Mississippi
			T. D.

Cut 12 1/4 in. hole to 105 ft. and run 108 ft. of 8 5/8 in. O.D. casing and cemented at bottom at 105 ft. with 80 sacks cement. Plug down at 3:00 P.M., June 20, 1968. Cut 7 7/8 in. hole to 2795. Hole dry and abandoned. Filled hole with mud to 100 ft, set plug and put in 25 sacks cement. Filled with mud to 40 ft., set plug and put in 10 sacks cement. Two sacks in rathole. Plugging completed at 9:00 P.M., by Gilbert Tomes, Holyrood, State Plugger, on June 24, 1968.

TOPS: Kansas City - 2131'      Mississippi - 2787'

Measurements taken from K.B.

**CERTIFICATE**

I, M. J. Flouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Kruger #1, located on the E/2 NW/4 SW/4 of Sec. 11-15-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

*M. J. Flouffe*  
 M. J. Flouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas