

14-15-2W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY GEORGE R HESS & LARRY MOORE RANCH INC
FARM Darold Nelson NO. 2

SEC. 14 T. 15 N. 2W
LOC. C E 1/2 NW

TOTAL DEPTH 2876'
COMM. 11-29 1967 COMP. 12-4-67
SHOT OR TREATED
CONTRACTOR Blackstone Drilling
ISSUED 1-20-68

COUNTY Saline

KANSAS



CASING

20 10
15 8 5/8" 125' cem w/ 95 sx
12 6
13 5 1/2" 2844' cem w/ 35 sx

1363' KB

PRODUCTION DRY/MISS



FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	38	Clay
38	to	125	Shale & Lime
125	to	730	Lime
730	to	1050	Lime & Shale
1050	to	1730	Shale & Lime
1730	to	2075	Lime & Shale
2075	to	2260	Shale & Lime
2260	to	2665	Lime
2665	to	2800	Lime & Shale
2800	to	2876	Shale & Lime
		2876	T. D.

Cut 12 1/4 in. hole to 126 ft. and run 128.50 ft. of 8 5/8 in. surface casing & cemented on bottom at 126 ft. with 85 sacks. Plug down at 3:00 P.M., November 29, 1967.
Cut 7 7/8 in. hole to 2876 ft. and run 2848 ft. of 5 1/2 in. casing and cemented with 35 sacks cement 32 foot off bottom at 2844 ft. Plug down at 9:00 P.M., December 4, 1967.

TOPS: Brown Lime - 2110' Kansas City - 2175' Mississippi 2795

Measurements taken from K.B.

that broken by miss. from 2798 to 2840'

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Nelson #2, located on the C-E/2 NW/4 of Sec. 14-15-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
H. J. Plouffe, President

sworn to before me a Notary Public in and for McPherson County, Kansas
day of December, 1967.



Ruth McVay
Ruth McVay - Notary Public

My commission expires: December 18, 1969.....