

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas

Plotted


STANOLIND OIL AND GAS CO.
 C.M. Wann No. 1

SEC. 12 T. 15 R. 20W.
 NW SW SE
 990' N of S.L. 330' E of WL.

Total Depth. 3716
 Comm. 5-22-35 **Camp.** 8-1-35
 Shot or Treated.
 Contractor.
 Issued. 9-14-35.

County. Ellis.

SEP 14 1935



CASING.

16" 79' 13" 979'

Elevation.

Production DRY

Figures Indicate Bottom of Formations.

sand and gravel	75	lime	3077
shale	84	sdv lime	3108
shale and shells	115	lime	3112
shale	200	lime hard	3165
sand	250	lime	3180
sand and shale	508	shale	3184
shale and shells	584	broken lime	3190
sand	847	lime soft	3196
shale	861	lime cored	3257
lime and shells	862	shale dark cored	3259
red sand	905	shale green cored	3267
shale all kinds	928	shale red cored	3271
red shale red bed	952	shale green cored	3273
red shale streaky	1007	lime cored	3275
shale red	1225	lime drilled	3283
anhydrite	1270	lime cored	3291
anhydrite and lime	1280	shale green cored	3293
shale red	1330	shale red cored	3298
shale red and green	1420	lime Lansing cored	3471
shale red	1450	shale red cored	3475
shale red and blue	1595	lime cored	3534
shale red & blue lime shells	1700	shale grey cored	3558
shale blue and lime shells	1802	shale red cored	3543
shale blue	1842	lime & red shale cored	3551
broken lime	1857	red shale and lime shells	3579
shale and lime shells	1880	chert red and lime and	
anhydrite	1946	shale red	3601
lime	2029	lime and shale dark cored	3616
lime blue	2037	sdv shale cored	3620
shale red sticky	2045	sand	3703
lime blue	2061	granite weathered cored	3711
broken lime and shale	2090	granite Fresh cored	3716
broken shale and lime shells	2111	Total Depth.	
shale brown and shells	2126	Lansing 3298-3538	
shale grey	2136	Base sand 3615-3703.	
shale blue and salt	2171		
lime	22 56		
broken lime	2288		
broken lime and sticky shale	2311		
sdv shale	2330		
lime	2370		
broken lime	2577		
shale and shells	2593		
broken lime	2606		
lime	2632		
sticky shale and lime shells	2663		
shale and lime shells	2707		
broken lime	2765		
shale	2825		
shale and shells	2876		
lime	2887		
broken lime	3059		
shale and shells	3074		

K.C.?