

35-15-20W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTERS DRILG. CO.
Farm- North "F" No. 1

SEC. 35 T. 15 R. 21W
C NE NW

Total Depth. 4290'
Comm. 3-25-63 Comp. 4-4-63
Shot or Treated.
Contractor.
Issued. 7-13-63

County Trego
KANSAS



CASING:
8 5/8" 165' cem w/90 sx.

Elevation. 2321' DF

Production. DRY

Figures Indicate Bottom of Formations.

| | |
|----------------|----------|
| post rock | 80 |
| shale | 167 |
| shale & shells | 465 |
| sand | 495 |
| shale & shells | 930 |
| lime | 965 |
| shale & shells | 1064 |
| sand | 1335 |
| shale & shells | 1638 |
| anhydrite | 1687 |
| shale & shells | 2300 |
| lime & shale | 2360 |
| lime | 2555 |
| lime & shale | 3490 |
| lime | 3585 |
| lime & shale | 3905 |
| lime | 3985 |
| lime & shale | 4115 |
| lime & chert | 4140 |
| lime & shale | 4174 |
| shale & sand | 4191 |
| sand & lime | 4241 |
| lime & shale | 4263 |
| lime & chert | 4290 RTD |
| Total Depth | |

TOPS: LOG

| | |
|-------------------------|------|
| Anhydrite | 1642 |
| Heebner | 3706 |
| Lansing | 3749 |
| Base Kansas City | 4007 |
| Marmaton | 4023 |
| Pawnee | 4090 |
| Base Pennsylvanian Sand | 4169 |
| Fort Scott | 4185 |
| Cherokee Sand | 4193 |
| Kutina Sand | 4224 |
| Mississippi | 4254 |