

HESS OIL COMPANY

P.O. BOX 1009
McPHERSON, KANSAS 67460-1009
(620) 241-4640

ACO-1 Completion Form Attachment

Eunice #1

120' N of SW SW SE, Section 32-15-22W

Trego County, Kansas

Elevation: 2387' KB

<u>FORMATION</u>	<u>TOP</u>	<u>DATUM</u>	
Anhydrite	1728'	(+659')	sample
Base Anhydrite	1766'	(+621')	sample
Heebner	3739'	(-1352')	log
Toronto	3758'	(-1371')	log
Lansing	3775'	(-1388')	log
Stark Shale	4003'	(-1616')	log
Base Kansas City	4251'	(-1664')	log
Marmaton	4080'	(-1693')	log
Pawnee	4150'	(-1763')	log
Fort Scott	4234'	(-1847')	log
Cherokee Shale	4255'	(-1871')	log
Mississippi	4384'	(-1997')	log
RTD	4370'	(-1998')	

DST #1:

Depth: 4255'-4355'. Times: 20-20- then pulled test. Blows: IF - strong blow off bottom of bucket in 2 min; ISI - no return blow. Recoveries: 325' mud, 1055' water. Pressures: IH 2139#, IF 433-600#, ISI 1244#, FF - - -, FSI - - -, FH 2136#