

P.O. BOX 1009
 McPHERSON, KANSAS 67460-1009
 (620) 241-4640

ACO-1 Completion Form Attachment

Coleen #1
 Approx. S2 SE SW
 290' FSL, 1870' FWL, Section 16-15-22W
 Trego County, Kansas
 API# 15-195-22281-00-00

Elevation: 2242' KB

<u>FORMATION</u>	<u>LOG TOP</u>	<u>DATUM</u>
Anhydrite	1591'	(+651')
Base Anhydrite	1631'	(+611')
Heebner	3586'	(-1344')
Toronto	3610'	(-1368')
Lansing	3626'	(-1384')
Stark Shale	3844'	(-1602')
Base Kansas City	3893'	(-1651')
Marmaton	3921'	(-1679')
Pawnee	3987'	(-1745')
Fort Scott	4070'	(-1828')
Cherokee Shale	4093'	(-1851')
Cherokee Sand	4179'	(-1937')
Mississippi	4241'	(-1999')
RTD	4270'	(-2028')
LTD	4268'	(-2026')

DST #1: Depth: 4094'-4188'

Times: 30-60-30-60

Blows: IF - 1/4" blow BOB in 9 min.
 FF - 1/4" blow BOB in 12 min.

Recoveries: 246' MCW (60% water, 40% mud)
 252' OWCM (5% oil, 10% water, 85% mud)
 126' OCM (5% oil, 95% mud)
 282' Mud w/oil spots

Pressures: IH 2061#, IF 36-257#, ISI 1274#, FF 259#-375#, FSI 1274#, FH 2041#

RECEIVED
 MAR 22 2005
 KCC WICHITA