

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


27-15-22W

Company- ROCKET EXPLORATION & DRILLING CO.
Farm- Squier No. 1

SEC. 27 T. 15 R. 22W
SW SW SW

Total Depth. 4340
Comm. 10-4-56 Comp. 10-17-56
Shot or Treated.
Contractor. Rocket Exploration & Drlg Co.
Issued. 11-17-56

County Trego
KANSAS



CASING:
8 5/8" 266' cem w/150 sx.

Elevation. 2330 D.F.

Production. Dry

Figures indicate Bottom of Formations.

post rock, clay	75
shale	195
sand	245
shale	1090
sand	1105
sand, shale	1150
red bed, sand	1690
anhydrite	1730
shale	2235
shale, lime strks	2305
lime, shale	2405
lime	2460
sand	2470
lime	2575
sand	2595
lime	2680
lime, sand	2765
lime	2800
shale, lime	3035
lime	3110
lime, shale	3328
lime	3388
lime, shale	3480
shale	3510
lime, shale	3788
lime	4203
lime, shale	4293
shale	4308
chert	4325
Miss.	4340
Total Depth	

Tops:
Heebner 3721
Lansing 3760
Fort Scott 4124
Cherokee 4202
Miss. 4318

DST 4230-4340 Open 1 hr., had weak
blow. Rec. 265' watery mud. IFP 220#,
FFP 380#, 20 SIP 1320#.