

35-15-24W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Lutters No. 1

SEC. 35 T. 15 R. 24W
C NE NE

Total Depth. 4463'
Comm. 3-30-57 Comp. 4-14-57
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 5-4-57

County Trego
KANSAS



CASING:
8 5/8" 309' w/250 sx cem.

Elevation. 2409' RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay-sand	309
shale-sand	500
shale-shells-sand	1400
shale-shells	1774
Anhydrite	1821
shale-shells	2425
lime-shale	3804
lime	4463
Total Depth	

TOPS:

Anhydrite	1774
Heebner	3754 ✓
Toronto	3773
Landing	3792
B/Kansas City	4087
Conglomerate	4398
Mississippi	4410

Core #1 4360-83 Cored 23'.
Rec. 19'.

Core #2 4383-4400' Cored 17'.
Rec. 15'

DST #1 4412-36 Open 1 hr. Rec.
95' watery mud. BHP 900#.