

35-15-25W

PICKRELL DRILLING COMPANY, INC.
WICHITA, KANSAS 67202

Memo to: ADDITION TO ACO-1

#1 Rauch 'B'
NE SE NW, Sec. 35-15S-25W
Trego County, Kansas

Backside squeezed w/400sx 60/40 Poz. 6% gel. Top of Dakota took cement at 650'. Perforated at 1000' and squeezed perms w/250sx 60/40 Poz. 6% gel. Max. Press. 2000# to break down, AIR prior to cementing 2 BPM @ 1000#. Scattered gamma-ray log indicated cement from surface to 660' and from 850' to 2340'.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1998

CONSERVATION DIVISION
Wichita, Kansas

NOV 17 1998

KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH