

ROTARY DRILLING LOG

35-15-26W  
ENE NW

APR 24 1971

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 3/5/71

Rotary Drilling Completed 3/16/71

LOCATION: Chapman "A" No. 2, C NE NW Section 35-15S-26W  
Gove County, Kansas

P 6.9 BOPD + water  
77. Scott  
6R48

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

Env. 2558' KB

CASING RECORD: Run 11 Jts. 8-5/8" Surface Casing set @ 226' KB. Cemented w/140 sacks. Completed 2 P.M. Circulated.

Run 141 Jts. 5-1/2" casing set at 4467'. Cemented w/80 sacks 50-50 Pozmix followed by 100 sacks common. Plug down @ 12:40 A.M., March 16, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		<u>C. F. S.</u>
70	Post Rock	
226	Shale & Shells, Cement	3965
1495	Shale	4020
1715	Sand	4046
1981	Shale	4080
2018	Anhydrite	4110
2056	Shale & Lime	4370
2510	Lime & Shale	4470
2785	Shale & Lime Stringers	
2930	Lime & Shale	
3196	Shale & Lime	
3456	Shale & Lime	
3625	Lime & Shale	
3965	Shale & Lime	
4110	Lime & Shale	
4115	Lime	
4455	Lime & Shale	
4470	Mississippian, RTD	

Slope Tests

2000
2500
3000
3500
4000

DDTD 4502

Log Info

Anhydrite	1976
Weller	3794
Lansing	3837
Kan. City	4006
Stark	4082
BKC	4138
Sawnee	4277
77 Scott	4344
Cherokee	4370
Conglomerate	4429
Mississippian	4439
" Dal	4458

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY