

PT

CONTRACTOR'S WELL LOG

OPERATOR: Foxfire Exploration, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: THORNBURG #2
 LOCATION: C E/2 E/2 SE, Section 35-15S-26W
 Gove County, Kansas
 SPUD DATE: 1/23/81
 COMPLETION DATE: 2/03/81

0	1894	Sand & Shale
1894	1962	Shale
1962	1998	Anhydrite
1998	3294	Shale
3294	3495	Shale & Lime
3495	3700	Lime
3700	4155	Lime & Shale
4155	4297	Lime
4297	4403	Shale & Lime
4403	4415	Lime
4415	4472	Lime & Chert
	4472	Rotary Total Depth

Spud hole @ 8:15 p.m., 1/23/81. Drilled 312' of a 12 1/4" hole. Ran 8 jts. of 8 5/8" - 24# used casing (tally 296.73) Set @ 304' K.B. Cemented with 200 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 5:00 a.m., 1/24/81.

T.D. @ 4472'. Set 1st Plug @ 980' with 60 sx. Set 2nd Plug @ 300' with 30 sx., Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx. 50-50 posmix, 6% gel. Plug was down @ 5:00 a.m., 2/03/81. State Plugger - Marion Schmidt.

SAMPLE TOPS:

Anhydrite 1962'
 B/Anhydrite 1998'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the THORNBURG #2, C E/2 E/2 SE, Section 35-15S-26W, Gove County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
 Jack L. Partridge, Asst. Sec./Treas.