

#1-34 Davis
34-15S-28W
Gove Co., KS

Tops:	Log Tops:	Datum:
Anhydrite	1893'	(+ 583)
B/Anhydrite	1928'	(+ 548)
Heebner	3638'	(-1162)
Lansing	3674'	(-1198)
Kansas City	3754'	(-1278)
Stark Sh.	3925'	(-1449)
Pleasanton	4004'	(-1528)
Marmaton	4023'	(-1547)
Labette	4176'	(-1700)
Cherokee	4211'	(-1735)
Mississippian	4282'	(-1806)
LTD	4332'	

DST #1 from 3752' – 3770' (70' zone)

Times: 30-30-30-30

1st op: 1/8" blow, dead in 19 minutes

2nd op: No blow

Recovered 10' of mud/gassy odor and good show of oil spots.

IFP: 68-55#, ISIP: 956#, FFP: 57-57#, FSIP: 915#

IHP: 1817# FHP: 1790#

DST #2 from 3838' – 3898' (140' & 160' zones)

Times: 30-45-45-60

1st op: 5"

2nd op: 5"

Recovered 58' of mud and 183' of watery mud (32% water). Total = 241'

IFP: 82-109#, ISIP: 1052#, FFP: 137-164#, FSIP: 997#

IHP: 1885# FHP: 1877#

DST #3 from 3922' – 3944' (KC 200' zone)

Times: 30-45-45-60

1st op: BOB 1 min.

2nd op: BOB 2 min:

Recovered 1954' GIP, 1120' of clean gassy oil (38 deg.grav.), 216' of gassy watery mud cut oil (35% O, 26% M, 20% G, 19% W) and 310' gas cut muddy water w/scum oil (5% G, 18% M, 77% W). 1646' Total liquid recovery.

IFP: 245-519#, ISIP: 683#, FFP: 642-656#, FSIP: 675#

IHP: 1926# FHP: 1913#

DST #4 from 4164' – 4268' (Ft.Scott, Cherokee)

Times: 30-30-30-30

1st op: Surface blow

2nd op: No blow

Recovered 20' mud with good gassy odor.

IFP: 96-96#, ISIP: 601#, FFP: 109-109#, FSIP: 164#

IHP: 2117# FHP: 2090#

**#1-34 Davis
34-15S-28W
Gove Co., KS**

DST #5 from 4282' – 4290' (Mississippian)

Times: 30-45-45-60

1st op: BOB 15 min.

2nd op: BOB 18 min.

Recovered 30' GIP, 35' clean gassy oil, 10' oil & gas cut muddy water, 124' slightly oil and gas cut muddy water, 248' of very slightly oil & gas cut muddy water, 248' of muddy water w/scum of oil.

665' TLR

IFP: 68-178#, ISIP: 1243#, FFP: 230-301#, FSIP: 1243#

IHP: 2090# FHP: 2104#