


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company—C. U. BAY
Farm—Royce "C" No. 1

SEC. 19 T. 15 R. 3W
SE SE NW

Total Depth. 3408
Comm. 1-13-52 Comp. 1-24-52
Shot or Treated.
Contractor. Lindsley Drlg Co.
Issued. 3-22-52

County Saline
KANSAS



CASING:

8 5/8" 313' cem w/225 sx.
5 1/2" 3401' cem w/ 75 sx.

Elevation 1306 D.F.

Production. 20.93 BO / 2.85 BW
(State Test 2-27-52)

Figures Indicate Bottom of Formations.

sand, clay	140
shells, shale	185
shale, sand, shells	305
anhydrite	313
shale, shells, lime	530
shale, shells	620
lime, shale	2885
lime Miss. & chat	2940
lime, shale	2975
lime Miss. & chat	3125
lime, shale	3160
lime Miss, shale	3225
lime, shale	3402
lime, shale	3408
Total Depth	

Tops:	
Lansing	2213
Mississippi	2862
Kinderhook	3167
Hunton	3298
Maquoketa S.	3346
Maquoketa	3400

D.P. — Rainbo oil.
D.D. 3406 1/2 — VSSO
D.D. 3408 / 5 hrs / 32 GO /
8 BW (probably
drilling wtr.)
1000 acid. Test 1/2 BOPH / 10% wtr