


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- W. E. SLUDNECKA ET AL  
Farm- Richter No. 2

SEC. 19 T. 15 R. 3W  
SW SW SW  
50' N 35' E. of Center

County Saline KANSAS

Total Depth. 3409  
Comm. 11-29-50 Comp. 12-11-50  
Shot or Treated.  
Contractor. E. K. Carey  
Issued. 5-24-52



CASING:  
8 5/8" 315' cem. w/210 sx  
5 1/2" 3406' cem. w/75 sx

Elevation. 1288 DF

Production. IPP 191 BO NW

Figures Indicate Bottom of Formations.

|                    |      |
|--------------------|------|
| rotary table, base |      |
| & cellar           | 8    |
| shale              | 55   |
| sand               | 70   |
| shale & shells     | 250  |
| lime & shale       | 315  |
| lime               | 510  |
| lime & shale       | 920  |
| shale & shells     | 1665 |
| lime               | 1780 |
| lime & shale       | 2075 |
| shale              | 2240 |
| lime K.C.          | 2605 |
| shale & lime       | 2630 |
| shale              | 2846 |
| lime, miss.        | 3162 |
| shale              | 3310 |
| lime Hunton        | 3340 |
| shale              | 3405 |
| lime               | 3409 |
| Total Depth        |      |

|                  |      |
|------------------|------|
| Tops:            |      |
| Miss. Lime       | 2851 |
| Kinderhook Shale | 3170 |
| Misener Sand     | 3306 |
| Hunton           | 3309 |
| Maquoketa Shale  | 3334 |
| Maquoketa Dolo.  | 3406 |

DST: 3406-09; open 1/2  
hr. rec. 250' oil & 20'  
oil cut mud; 15 min.  
BHP 1212 7/8

Formations K.B.