

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE GREENLAND OIL CO.

SEC. 19 T. 15 R. 3W

FARM Larson


NO. 1

LOC. SW SW SE

TOTAL DEPTH 3590 DF PB 3424 DF
COMM. 10-28-50 COMP. 12-19-50
SHOT OR TREATED
CONTRACTOR Jackson Drlg Co.
ISSUED 3-10-51

COUNTY Saline

KANSAS



CASING

8 5/8" 303' cem w/150 sx
5 1/2" 3386' cem w/ 75 sx

ELEVATION 1284 DF

PRODUCTION Pot. 44 bbls, 28% wt

ALL MEASUREMENTS FROM TOP OF

DERRICK FLOOR

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	9
clay	25
sand	35
shale, shells	250
shale, lime	303
anhydrite	390
shale, shells	410
lime	540
salt	580
lime	905
lime, shale, salt	1205
lime	1530
lime, shale	1947
lime	1965
lime, shale	2120
shale	2265
lime, shale	2360
lime	2395
shale	2535
lime	2485
lime, shale	2835
shale	2854
lime	3175
lime, shale	3254
shale	3305
lime, shale	3375
shale	3385
lime	3391

Total Depth

Plugged back to 3424

Tops:

Mississippi	2839
Hunton	3284
Maquoketa Shale	3320
Maquoketa Dolomite	3383
Viola	3444

DST: 3386-91. Recovered
25' free oil - 60' heavy
oil cut mud, open 1 hr.

Acid 1000 gals. - 35 bbls
oil in 24 hrs.