

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE GREENLAND OIL CO.

SEC. 19 T. 15 R. 3W

FARM Larson

NO. 2

LOC. SW NW SE

TOTAL DEPTH 3650 DF  
 COMM. 12-16-50 COMP. 1-17-51  
 SHOT OR TREATED  
 CONTRACTOR Jackson Drilling Co.  
 ISSUED 3 - 10 -51

COUNTY Saline



CASING

8 5/8" 298' cem w/300 sx.  
 5 1/2" 3432' cem w/100 sx.

ELEVATION 1279 DF

PRODUCTION Pot. 11 bbls,  
 10% water

ALL MEASUREMENTS FROM TOP OF DERRICK FLOOR. FIGURES INDICATE BOTTOM OF FORMATIONS

clay	10
red bed	100
red bed, shells	240
red bed, anhydrite	265
shale	298
anhydrite	360
lime	395
lime, shale	505
lime	545
salt, shale	575
lime, shale	1115
shale, shells	1235
lime, shale	1725
lime	1785
lime, shale	2150
shale	2225
lime broken	2230
shale	2240
shale, lime	2255
lime	2275
shale, lime	2360
lime	2470
shale, lime	2645
lime	2680
shale, shells	2837
lime	3175
shale, lime	3456
lime, cherty	3527
lime, sandy dolo.	3571
lime	3579
shale, lime	3597
lime, chert	3609
dolomite sdy, shale	3630
lime arbuckle	3650
Total Depth	

Acid 1000 gals. - swabbing  
 1 1/2 barrels oil per hour.  
 Dowell service -3000 gallons.

Tops:  
 Mississippi 2835-3160  
 Hunton 3274  
 Viola 3377  
 Arbuckle 3628

DST: 3381-89. Rec. 37'  
 heavily oil cut mud -  
 open 1 hr.

Perforated casing 3379 -91  
 w/36 holes - show little  
 oil.