

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


Company- STERLING DRILLING COMPANY, et al  
Farm- Holmquist No. 1

SEC. 29 T. 15 R. 3W  
SW SW SE

Total Depth. 3380 KB  
Comm. 7-15-53 Comp. 8-4-53  
Shot or Treated.  
Contractor. Sterling Drlg Co; K C Drlg Co.  
Issued. 9-19-53

County Saline

KANSAS



Elevation. 1291

Production. Pmp 50 bbls & no wtr

CASING:

13 5/8" 115' cem w/125 sx  
5 1/2" 3377' cem w/ 50 sx

Figures Indicate Bottom of Formations.

surface clay	60
shale, shells	340
lime	845
lime, shale	2245
lime	2350
lime, shale	2480
lime	2620
lime, shale	2705
shale	2847
lime	3125
shale	3375
lime	3380 KB
Total Depth	

Tops: Scout.  
Maquoketa dolomite 3375

Cable Tool Record: Rigged up cable tools. Swabbed out drilling mud. Drilled 29' of cement & shoe to T.D. of 3380 K.B. 8 hr fillup, 400' oil, no water, Swbd hole down. Acidized down casing w/1000 gals of Dowell Acid. Left well over night. Swbed well down & swabbed well at rate of 1 BOPH, pulling s wab once evey hr off bottom. Acidized down casind w/1000 gals Dowell Acid. Left well over night. Swabed well down & swabbed at rate of 2 BOPH. Left well over night. Found 1000' of fluid in hole at 8 a.m. Bailed acid water off bottom. Moved out cable tools. Ran rods & tbg w./ pulling unit. P.O.P.