

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY E. K. CAREY & JOHNSON BROS.

SEC. 30 T. 15 R. 3W

FARM Larson "A"

NO. 1

LOC. CN<sup>1</sup>/<sub>2</sub> NE SW

TOTAL DEPTH 3402

COMM. 2-24-51


COMP. 3-10-51

SHOT OR TREATED

CONTRACTOR E. K. Carey

ISSUED 4-14-51

COUNTY Saline



CASING

8 5/8" 318' cem. w/250 sx. circ.  
5 1/2" 3398' cem. w/75 sx.

ELEVATION 1287 D.F.

PRODUCTION Pot 465 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

rotary table, base & cellar	8
shale	60
sand	65
shale	265
shale & shells	318
lime & shale	860
shale & shells	1515
shale & lime	1740
lime	2063
shale & lime	2085
shale & shells	2185
shale	2218
lime	2555
lime & shale	2705
shale	2850
lime	3172
shale	3305
lime	3329
shale	3398
lime	3402 RTD
Total Depth	

Tops:	
Miss. lime	2850
Kinderhook shale	3158
Misener sand	3304
Hunton	3307
Maquoketa shale	3335
Maquoketa dolo.	3397
Pay	3397

D.S.T. 3398-3402 Op. 30 min.  
Blowing from bottom of 5 ga. bucket  
in 3 min. Rec. 310' free oil 15 min.  
BHP - 1145#. Initial flowing press. 18#.  
Final flowing press. 139#.