

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- REPUBLIC NATURAL GAS COMPANY
Farm- Larson "B" No. 6

SEC. 30 T. 15 R3W

~~CN 1/2 N 1/2~~
CN 1/2 N 1/2 NW

Total Depth. 3443
Comm. 12-28-52 Comp. 1-15-53
Shot or Treated.
Contractor. E. K. Carey
Issued. 12-5-53

County Saline
KANSAS



CASING:

8 5/8" 310' cem. w/330 sx
5 1/2" 3443' cem. w/ 50 sx

Elevation. 1287

Production. 100 BO & 19% wtr

Figures indicate Bottom of Formations.

cellar	8
clay & shale	37
sand	46
shale & shells	64
lime & shale	310
lime	700
shale & lime	1700
lime	2038
sandy lime	2104
shale & lime	2155
shale	2220
lime	2260
lime sandy	2270
lime	2575
lime & shale	2675
lime	2710
lime & shale	2845
lime	3167
shale & lime	3170
shale	3298
lime	3330
shale maquoketa	3393
dolomite maquoketa	3443
Total Depth	

SCOUT TOPS:

Hunton	3301
Maquoketa Dolomite	3392

Core #1 3393-3421' full rec.
Core #2 3421-3443' 17' rec.