


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas

Company - E. K. CAREY  
 Farm - Gunnerson No. 1

SEC. 34 T. 15 R. 3W  
 CN/2 NE SW

Total Depth. 3381 KB  
 Comm. 8-19-50 Comp. 9-2-50  
 Shot or Treated.  
 Contractor. E. K. Carey  
 Issued. 9-30-50

County. Saline  
 KANSAS



CASING:  
 8 5/8" 300' cem /225' sx.

Elevation. 1283 DF

Production. dry

Figures Indicate Bottom of Formations. K.B.

cellar	5
clay	14
shale	25
sand	45
shale	80
shale, shells	240
sand, shale	260
lime	300
shale, lime	1115
shells, shale	1400
shale, lime	2100
shale	2154
lime	2390
shale, lime	2535
shale	2674
shale, lime	2770
shale	2798
lime	3080
shale, lime	3225
lime	3253
shale, lime	3270
shale	3308
lime	3381
Total Depth KB	

Tops: KB	
Lansing- K C	2152
Base Kansas City	2518
Cherokee Shale	2648
Mississippi Lime	2786
Kinderhook shale	3068
Hunton	3228
Maquoketa Shale	3238
Maquoketa Dolomite	3307
Viola	3360

Pay 3370-81

DST: 3308-24. Tool open 30 min. Recovered 35' Rotary mud. No BHP  
 DST: 3370-81. Tool open 1 hr. Good blow. Recovered 10' oil - 55' heavy oil cut mud - 60' light oil cut mud and 90' salt water.  
 BHP - 1235#