


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHALDON & WEST ET AL
Farm- M. Johnson No. 1

SEC. 32 T. 15 R. 3W
SW SW SE

Total Depth. 3381'
Comm. 3-25-53 Comp. 4-6-53
Shot or Treated.
Contractor. Salina Drlg. Corp., Inc.
Issued. 6-29-57

County Saline
KANSAS



CASING:
8 5/8" 348'
5 1/2" 3377' w/50 sx cem.

Elevation. 1303' DF

Production. 155 B0 & vssw

Figures indicate Bottom of Formations.

NO DRILLERS LOG AVAILABLE.

All Meas. fr RB.

sand	2854-56
free sand grains	2856-60
chert	2860-66
limey dolomite	2883-88
dolomite	2888-2905
dolomite	2916-33
chert-dolomite	2954-64
solomitic chert	2985-3022
chert dolomite-	3022-68
solomitic-chert	3080-97
brwn sand	3302-03
dolomite	3303-05
dolomite	3305-09
chert	3309-16
dolomite-shows of free oil & stain; chert- fair shows free oil	3376-81
Total Depth	3381

TOPS:

Burgess sand	2854
Mississippian	2860
Kinderhook shale	3147
Misener sand (shaly)	3302
Hunton	3303
Maquoketa shale	3316
Maquoketa dolomite	3376

DST #1; 3377-81; opne 1 hr., opened
w/fa ir blow gradually increasing
to good blow which continued through-
out test; rec. 70' HOCM & 60' free
oil no wtr; 20 min. BHP 825#; FFP 55#.