

22-15-3W

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY VANDEVER PETROLEUM

SEC. 22 T. 15 R. 3W

FARM Stroback

NO. 1

LOC. C NE SE

TOTAL DEPTH 3490

COMM. 7-12-67

COMP. 7-20-67


SHOT OR TREATED

CONTRACTOR Blackstone Drlg.

ISSUED 9-9-67

COUNTY Saline

KANSAS



CASINO


20	10	
15	8	5/8" 157' cem w/ 100 sx
12	6	
13	5	

ELEVATION 1267' KB

PRODUCTION DRY/ ARB

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	35	Shale & Sand	TOPS: LOG	
35	to	300	Shale & Shells	Kansas City	2096
300	to	340	Lime	Mississippi	2762
340	to	950	Lime & Shale	Kinderhook	3028
950	to	1700	Shale & Lime	Hunton	3184
1700	to	1875	Lime	Maquoketa shale	3207
1875	to	2121	Lime & Shale	Maquoketa Dolomite	3276
2121	to	2500	Kansas City	Viola	3330
2500	to	2740	Lime & Shale	Simpson shale	3444
2740	to	2765	Shale & Lime	Simpson sand	3465
2765	to	3000	Mississippi	Arbuckle	3482
3000	to	3030	Kinderhook		
3030	to	3085	Shale		
3085	to	3185	Hunton		
3185	to	3328	Shale & Lime		
3328	to	3391	Viola Lime		
3391	to	3465	Lime		
3465	to	3490	Simpson		
		3490	T. D.		



Cut 12 1/4 in. hole to 157 ft. and run 160.65 ft. of 8 5/8 in. O.D. casing and cemented at 157' with 100 sacks cement. Plug down at 2:30 P.M., July 12, 1967. 7 7/8 in. rathole from 157 ft. to 300'. Cut 7 7/8 in. hole to 3490 ft. Hole dry & abandoned. Set first plug at 150 ft. put in 20 sacks cement. Filled hole with mud to 40 ft. set second plug, put in 10 sacks cement. 2 sacks in rathole. Job completed at 10:00 P.M., July 20, 1967 by Gilbert Tenan, State Plugger, Holyrood, Kansas.

TOPS: Kansas City - 2121' Mississippi - 2765' Kinderhook - 3030'
Hunton - 3185' Maquoketa - 3276' Viola - 3328' Simpson Sand - 3465'

Measurements taken from K.B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Stroback #1, located on the C-NE/4 SE/4 of Sec. 22-15-3W, Saline County, Kansas as reflected by the files of BLACKSTONE DRILLING, INC.

H. J. Plouffe, President