

Geological Survey
WICHITA, BRANCH

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

March 18, 1974

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1974
24-15-3W
CONSERVATION DIVISION
Wichita, Kansas

COMPANY:

Cal Jones

CONTRACTOR:

Blackstone Drilling, Inc.

FARM:

Carlin #1

LOCATION:

C S/2 NW, Sec. 24-158-3W,
Saline County, Kansas

COMMENCED:

March 8, 1974

COMPLETED:

March 18, 1974

ELEVATION:

0	to	200	200	Sand
200	to	415	415	Line
415	to	715	715	Line & Shale
715	to	1000	1000	Line
1000	to	1260	1260	Line & Shale
1260	to	1370	1370	Shale & Line
1570	to	2495	2495	Line
2495	to	2570	2570	Line & Shale
2570	to	2700	2700	Shale & Line
2700	to	2875	2875	Line
2875	to	2955	2955	Mississippi
2955	to	3065	3065	Shale
3065	to	3275	3275	Shale & Line
3275	to	3375	3375	Line
3375	to	3400	3400	Simpson
		3400	3400	T. D.

Cut 12 1/4 inch hole to 281' and run 283' of 6 5/8 inch surface pipe, cemented with 175 sacks of cement at 281'. Plug down at 12:00 Noon, March 10, 1974. Cut 7 7/8 inch hole to 3400'. Run 3428' of 6 1/2 inch casing, cemented at 3397', 3 ft. off bottom with 75 sacks of cement. Plug down at 6:00 a. m., March 18, 1974.

TOPS:

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Carlin #1, located on the C S/2 NW/4, Section 24-158-3W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.


Charles D. Johnson, Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 18th day of March, 1974.