

BEREN CORPORATION
Tuttle No. 1
NW NW NE, Sec. 30-15S-31W
Gove County, Kansas

Surface Casing: 300' of 8-5/8" 28#
used casing, cemented w/200 sacks
60-40 Posmix, 2% Gel, 3% cc
2/5/77

FORMATION

DEPTH

Surface Hole	0	-	300	
Shale & Sand	300	-	1235	
Shale	1235	-	1645	
Blaine	1645	-	1658	
Shale & Sand	1658	-	1775	
Shale	1775	-	1990	
Sand	1990	-	2100	
Shale	2100	-	2347	
Anhydrite	2347	-	2389	
Shale & Lime	2389	-	3185	
Lime & Shale	3185	-	3965	
Lime	3965	-	3992	
Lime & Shale	3992	-	4036	
Lime	4036	-	4135	
Lime & Shale	4135	-	4170	
Lime	4170	-	4275	
Lime & Shale	4275	-	4320	
Lime	4320	-	4655	R.T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 24th day of February, 1977.

Ella Priess
Ella Priess, Notary Public

