

TICKET NO. 77

**SHOLOM DRILLING INC.**

DATE 3-14-63

LEASE NAME Davidson WELL NO. 3 TEST NO. 1 LEASE OWNER ROBINOWITZ OIL Co

LOCATION 33 15 11 FIELD \_\_\_\_\_ COUNTY Russell STATE Kansas

TOTAL DEPTH	<u>2840</u>	INITIAL CLOSED IN TIME	<u>30</u>	MIN.
HOLE SIZE	<u>7 7/8</u>	TOOL OPEN FLOW PERIOD	<u>120</u>	MIN.
RATHOLE SIZE		FINAL CLOSED IN TIME	<u>30</u>	MIN.
TOP PACKER DEPTH	<u>2776</u>	INITIAL HYDRO MUD PRESSURE	<u>1590</u>	LBS.
BOTTOM PACKER DEPTH	<u>2782</u>	INITIAL CLOSED IN PRESSURE	<u>1060</u>	LBS.
SIZE PACKER	<u>6 3/4</u>	INITIAL FLOW PRESSURE	<u>100</u>	LBS.
LENGTH ANCHOR	<u>58</u>	FINAL FLOW PRESSURE	<u>180</u>	LBS.
MUD WEIGHT	<u>10.2</u>	FINAL CLOSED IN PRESSURE	<u>950</u>	LBS.
VISCOSITY	<u>40</u>	FINAL HYDRO MUD PRESSURE	<u>1590</u>	LBS.

REMARKS Very weak blow for two hours

Rec 135# ft muddy water no show of oil

TESTER R W Sanders

WITNESSED BY \_\_\_\_\_



TICKET NO. 78

SHOLOM DRILLING INC.

DATE 3-15-63

LEASE NAME Davidson

WELL NO. 3

TEST NO. 2

LEASE OWNER Robinowitz Oil Co

LOCATION 33 15 11

FIELD \_\_\_\_\_

COUNTY Russell

STATE Kansas

TOTAL DEPTH	<u>2961</u>	INITIAL CLOSED IN TIME	_____	MIN.
HOLE SIZE	<u>7 7/8</u>	TOOL OPEN FLOW PERIOD	<u>60</u>	MIN.
RATHOLE SIZE		FINAL CLOSED IN TIME	<u>30</u>	MIN.
TOP PACKER DEPTH	<u>2849</u>	INITIAL HYDRO MUD PRESSURE		LBS.
BOTTOM PACKER DEPTH	<u>2855</u>	INITIAL CLOSED IN PRESSURE		LBS.
SIZE PACKER	<u>6 3/4</u>	INITIAL FLOW PRESSURE	<u>125</u>	LBS.
LENGTH ANCHOR	<u>103</u>	FINAL FLOW PRESSURE	<u>175</u>	LBS.
MUD WEIGHT	<u>10.1</u>	FINAL CLOSED IN PRESSURE	<u>1000</u>	LBS.
VISCOSITY	<u>41</u>	FINAL HYDRO MUD PRESSURE		LBS.

REMARKS:

Strong blow tru out test

Rec 1308 ft muddy water slightly gas cut

TESTER Carl Swanson

WITNESSED BY \_\_\_\_\_



TICKET NO. 79

**SHOLOM DRILLING INC.**

DATE 3-16-63

LEASE NAME Davidson WELL NO. 3 TEST NO. 4 LEASE OWNER Robinowitz Oil Co

LOCATION 33 15 11 FIELD \_\_\_\_\_ COUNTY Russell STATE Kansas

TOTAL DEPTH	3145	INITIAL CLOSED IN TIME	20	MIN.
HOLE SIZE	7 7/8	TOOL OPEN FLOW PERIOD	120	MIN.
RATHOLE SIZE		FINAL CLOSED IN TIME	30	MIN.
TOP PACKER DEPTH	29600	INITIAL HYDRO MUD PRESSURE	1700	LBS.
BOTTOM PACKER DEPTH	2966	INITIAL CLOSED IN PRESSURE	1000	LBS.
SIZE PACKER	6 3/4	INITIAL FLOW PRESSURE	200	LBS.
LENGTH ANCHOR	189	FINAL FLOW PRESSURE	460	LBS.
MUD WEIGHT	10.3	FINAL CLOSED IN PRESSURE	840	LBS.
VISCOSITY	38	FINAL HYDRO MUD PRESSURE	1700	LBS.

REMARKS:

Weak blow for 2 hrs

Rec 480° muddy water

TESTER Harold Cheney

WITNESSED BY \_\_\_\_\_



TICKET NO. 80

**SHOLOM DRILLING INC.**

DATE 3 18 63

LEASE NAME Davidson WELL NO. 3 TEST NO. 5 LEASE OWNER Robinowitz Oil Co

LOCATION 33 15 11 FIELD \_\_\_\_\_ COUNTY Russell STATE Kansas

TOTAL DEPTH	<u>3289</u>	INITIAL CLOSED IN TIME	<u>20</u>	MIN.
HOLE SIZE	<u>7 7/8</u>	TOOL OPEN FLOW PERIOD	<u>120</u>	MIN.
RATHOLE SIZE		FINAL CLOSED IN TIME	<u>30</u>	MIN.
TOP PACKER DEPTH	<u>3227</u>	INITIAL HYDRO MUD PRESSURE	<u>1820</u>	LBS.
BOTTOM PACKER DEPTH	<u>3233</u>	INITIAL CLOSED IN PRESSURE	<u>1000</u>	LBS.
SIZE PACKER	<u>6 3/4</u>	INITIAL FLOW PRESSURE	<u>140</u>	LBS.
LENGTH ANCHOR	<u>55</u>	FINAL FLOW PRESSURE	<u>500</u>	LBS.
MUD WEIGHT	<u>10.2</u>	FINAL CLOSED IN PRESSURE	<u>980</u>	LBS.
VISCOSITY	<u>43</u>	FINAL HYDRO MUD PRESSURE	<u>1820</u>	LBS.

REMARKS:

Weak blow for 2 hrs

Res 60, slightly oil cut mud. 240 ft oil cut mud 600 muddy oil

TESTER R W Sanders

WITNESSED BY \_\_\_\_\_

