

PI

22-15-35W

DRILLER'S LOG

15-109-20185

COMPANY: Cities Service Company

SEC. 22 T. 15S R. 35W

WELL NAME: Plummer "A" #1

LOC. NW NW NW

COUNTY: Logan

RIG NO. #2

TOTAL DEPTH 5385'

ELEVATION

COMMENCED: 9-23-81

COMPLETED: 10-11-81

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 355' w/300 sx. Class A, 3% cc.

PRODUCTION: 5 1/2" @ 5380' w/300 sx. 50/50 poz., 20 bbls saltwater flush,
 10% salt, 3/4# of 1% CFR2 and 350 sx. Lite, 10% salt, 3/4# of
LOG
 1% CFR2.

(Figures Indicate Bottom of Formations)

Clay, Sand & Shale	356
Shale	1200
Lime & Shells	1303
Lime & Shale	1554
Shale & Lime	1860
Lime & Shale	3410
Lime	3640
Lime & Shale	3875
Lime	4582
Lime & Shale	4650
Lime	4870
Lime & Sand	4969
Lime	5231
Lime & Shale	5333
Shale & Lime	5385
<u>ROTARY TOTAL DEPTH</u>	<u>5385</u>

STATE OF Kansas)
 COUNTY OF Sedgwick)

SS:

RECEIVED
 STATE CORPORATION COMMISSION

NOV 25 1981

CONSERVATION DIVISION
 Wichita, Ks.