

8/21/83

19-15-38ad

CONFIDENTIAL

Compt. _____

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

W88-21-P1

14

SIDE TWO
 OPERATOR Sunburst Exploration Co., INCASE Linder "B" SEC. 19 TWP. 15 RGE. 38
 ACO-1 WELL HISTORY (E)
 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
Sand 0 70				
Shale and Sand 70 190				
Sand 190 1204				
Sand and Shale 1204 1656				
Sand and Clay 1656 1700				
Shale and Chalk 1700 1800				
Shale and Red Bed 1800 2328				
Sand and Shale 2328 2375				
Shale 2375 2619				
Anhydrite 2619 2642				
Shale 2642 3232				
Shale and Lime 3232 4549				
Lime 4549 4562				
Lime and Shale 4562 4820				
Lime 4820 4905				
Lime and Shale 4905 5132				
Lime 5132 5295				
T.D. 5295				
DST #1 4511-4562				
30" 30" 30" 30"				
Rec. 10' Mud				
IFP 54-54# FFP 54-54#				
ISIP 887# FSIP 810# Temp. 122°				
DST #2 4843-4905				
30" 45" 45" 60"				
Rec. 752' Mdy SW (Chlds. 27,000)				
IFP 109-272# FFP 272-382#				
ISIP 1161# FSIP 1161# Temp. 130°				
DST #3 5186-5292				
30" 45" 45" 45"				
Rec. 2385' SW (Chlds. 10,000)				
IFP 436-909# FFP 986-1205#				
ISIP 1237# FSIP 1237# Temp. 141°				
If additional space is needed use Page 2, Side 2				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13 3/8"	8 jts.	48#	324'	Common	400	3% C.C. 2% Gels

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

WELL LOG

LINDER 'B' #1
C SE Sec 19-15S-38W
Wallace County, KS

CONFIDENTIAL

Pl

NAME OF OPERATOR: Sunburst Exploration # 5005
708 One Main Place
Wichita, KS 67202

DATE COMPLETED: 8-21-83

<u>FROM</u>	<u>TO</u>	
0	70	Sand
70	190	Shale and Sand
190	1204	Sand
1204	1656	Sand and Shale
1656	1700	Sand and Clay
1700	1800	Shale and Chalk
1800	2328	Shale and Red Bed
2328	2375	Sand and Shale
2375	2619	Shale
2619	2642	Anhydrite
2642	3232	Shale
3232	4549	Shale and Lime
4549	4562	Lime
4562	4820	Lime and Shale
4820	4905	Lime
4905	5132	Lime and Shale
5132	5295	Lime
5295		T.D.

STATE OF KANSAS


COUNTY OF BARTON ss

RELEASED


Date: SEP 1 1984

FROM CONFIDENTIAL

George E. Miller, Jr., President of Blue Goose Drilling Company, Inc. being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.


George E. Miller, Jr.

Subscribed and sworn before me this 24th Day of August 1983.




Helen C. Standley, Notary Public