

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - MESSRS. J. A. DAVIS & J. H. CHILD
Farm - Dahlsten No. 3

SEC. 24 T. 15 R. 4W
SE SW SE

Total Depth. 3411' 8"

Comm. 4-27-51

Comp. 6-1-51


Shot or Treated.

Contractor. Storling Drlg. Co.

Issued. 7-14-51

County. Saline

KANSAS



Elevation. 1293 DF

Production. 114 Bbls. oil / 5%
water

CASING:

8 5/8" 320' cem. w / 225 sx

5 1/2" OD 3418' cem. w / 50 sx, 3' O.B.

Figures Indicate Bottom of Formations.

surface clay & shale	125
shale	315
Anhydrite	345
limo	475
limo & shale	620
limo	1030
shale & shells	1600
limo & shale	2150
shale	2250
limo	2550
limo & shale	2640
limo	2790
limo & shale	2863
limo, Mississippi	2880
limo	3040
limo & chert	3125
limo	3150
limo & shale	3200
shale	3275
shale & lime	3325
shale	3408
limo	3411, RTD
limo	3411' 8"
Total depth	

Scout Tops:

Kinderhook 3375

Maquoketa dolomite 3408

Cable Tools Record:

Drilled plug. Cleaned out to
bottom. Swab test showed

well making 1 bbl. oil per hr.

Drilled 8 in. of new hole. Shot
with 16 shots between 3407-3410 1/2'.

Cleaned out to bottom. Swab test
showed well making 3 bbls. oil
per hr. Well put on pump.