

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- E. K. CAREY
Farm- G. Johnson

No. 1

SEC. 25


T. 15

R. ~~5~~ ⁴⁰

NE SE NW

Total Depth. 3415 K.B.
Comm. 6-25-51 Comp. 7-8-51
Shot or Treated.
Contractor. E.K. Carey
Issued. 9-15-51

County Saline
KANSAS



Elevation. 1296 D.F.

Production. 116 bbls / 1% water

Figures indicate Bottom of Formations. K.B.

rotary base & cellar	8
soil, clay	30
sand	40
shale, shells	135
shale, lime	314
lime, shale	760
salt	763
lime, shale	1155
shale, shells	1310
shale, lime	2242
lime	2560
shale, lime	2785
shale, shells	2906
lime	3175
shale	3225
shale, lime	3300
shale	3413 $\frac{1}{2}$
lime (Maquoketa)	3415
Total depth	

Tops:

Mississippi lime	2883
Kinderhook shale	3184
Misener sand	3322
Hunton	3327
Maquoketa Shale	3339
Maquoketa dolomite	3413 $\frac{1}{2}$

Drill Stem test 3413-15 (2" of anchor) packer would not seat in four attempts. Run 4 $\frac{1}{2}$ " casing 3414, 1 foot off bottom.

8 5/8 & 4 $\frac{1}{2}$ " head 6.40' below K.B.