


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E. K. CAREY DRLG.
Farm- Johnson No. 2

SEC. 25 T. 15 R. 4W
SE SE NW

Total Depth. 3409
Comm. 2-6-52 Comp. 2-21-52
Shot or Treated.
Contractor. E. K. Carey
Issued. 4-19-52

County Saline
KANSAS



Elevation. 1291 K.B.

Production. 213 bbls ~~no~~ wtr.

CASING:

13" 83' cem. w/100 sx.
8 5/8" 327' cem. w/200 sx.
5 1/2" 3407 1/2' cem. w/75 sx.

Figures indicate Bottom of Formations.

Meas. K.B.	
cellar	8
soil	18
sand	76
shale	83
shells & shale	165
lime & shale	235
shale & gyp L.C. zone	280
lime & shale	760
lime	915
lime & shale	1040
shale & shells	1730
lime & shale	1820
lime	1910
lime & shale	2010
shale & lime	2235
lime	2595
shale & lime	2870
shale	2878
lime	3135
lime Miss	3170
lime	3186
shale & lime	3290
shale	3328
lime	3340
shale & lime	3407 1/2
Maquoketa dolo.	3409 RTD
Total Depth	

Tops:	
Mississippi	2868
Kinderhook	3178
Hunton	3316
Maquoketa shale	3338
Maquoketa dolo.	3407 1/2