

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas

Company - E. K. CAREY

Farm - O'Berg

No. 1

SEC. 35 T. 15 R. 4W
NE NE NE

Total Depth. 3416

Comm. 5-7-51

Comp. 5-20-51


Shot or Treated.

Contractor. E. K. Carey

Issued. 9-15-51

County. Saline

KANSAS



CASING:

8 5/8" 318' cen. w/250 sx

4 1/2" 3412 1/2' cen. w/75 sx

Elevation. 1302 DF

Production. 1182 BO

Figures indicate Bottom of Formations. K.B.

base & cellar	8
shale	40
sand	50
shale	75
shale & shells	246
sand	254
lime & shale	950
shale & shells	1425
shale & lime	1525
shale & shells	1640
lime & shale	2260
lime	2348
lime sandy	2380
lime	2610
shale & lime	2790
shale	2895
lime	3185
shale	3200
shale & lime	3260
shale	3412
lime	3416
Total Depth	

Tops:

Lansing-K.C.	2251
Base-Kansas City	2609
Cherokee Shale	2753
Burgess Sand	2895
Miss. Lime	2906
Kinderhook Shale	3164

DST: 3413-16 (3' anchor)
 open 1/2 hrs. Started with
 good #10 blow, increased to
 strong blow in 2 mins. OWS
 (blow on bottom of bucket)
 recover 110' oil cut mud and
 450' oil, 20 min. BHP 1298 #
 Init. Flow pr. 35# Final Flow
 press. = 210#.