

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - THE ELDORADO REFINING CO.
Farm - Larson No. 1

SEC. 35 T. 15 R. 4W
SE SW SE

Total Depth. 3444
Comm. 7-15-51 Comp. 8-6-51
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 9-15-51

County. Saline

KANSAS



CASING:
8 5/8" 352' cen. w/ 195' sx
5 1/2" 3441' cen. w/ 75' sx

Elevation. 1331 DF

Production. 183 BO & 18% wtr.

Figures Indicate Bottom of Formations.

surface clay & sand	95
sand & shale	295
shale	355
shale & shells	375
anhydrite	390
shale, sand & lime	530
lime & shale	755
lime	945
lime & shale	1845
lime	2120
shale & lime	2310
lime	2470
shale & lime	2520
lime	2650
shale	2740
shale & lime	2785
shale	2955
lime	3200
lime & shale	3235
shale	3440
lime	3444
Total Depth	

Tops: D.F.
Maquoketa Dolomite 3438

DST: 3439-42, open 30 min.
good blow, rec. 450' oil.
Init. flow press. 35#; final
flow press. 185#; S.I.P. 1235#.

D. P. & C. O. to T.D. 3442 D.F.;
F. U. 2850' OIH/24 hrs. F. U.
11 BO & 1 BW/1 hrs.