


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- The EL DORADO REFINING COMPANY
Farm- Larson No. 3

SEC. 35 T. 15 R. 14W
CW/2 W/2 SE

Total Depth. 3423
Comm. 6-21-52 Comp. 7-8-52
Shot or Treated.
Contractor. Shields Drilling Co., Inc.
Issued. 8-16-52

County Saline
KANSAS



CASING:
12 3/4" 68' p.
8 5/8" 315' : cem w/300 sx
5 1/2" 3422' cem w/ 60 sx

Elevation. 1313 DF

Production. 140 BOPD, no wtr

Figures indicate Bottom of Formations.

surface, shale	106
shale, chip	300
chip, anhydrite	354
anhydrite, lime	410
lime, snad	640
sand, shale brkn	770
lime, shale	920
lime, shale, salt	1175
shale, shells, salt	1475
shale, shells, lime broken	1760
shale, lime	2330
lime	2455
lime, shale streaks	2525
lime, shale	2845
shale	2909
lime, shale	3057
lime, shells, shale	3117
lime cherty, shale	3142
lime, shale	3250
shale	3423 D.F.
Total Depth	3420 D.F.

Tops: D.F.
Miss. 2912
Kinderhook 3187
Maquoketa shale 3356
Maquoketa dolomite 3419

D.P. & C.O. to 3420, T.D.D.F.
75' OIH: D.S. 3421: 125' OIH
3/4 hrs. 250 OIH/1 hr; F.U.
2000' OIH/16 hrs. § 57 BO/16 hrs.