

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Muldeck, Wichita, Kansas

Company- E. K. CAREY
Farm- Lofgren No. 3

SEC. 36 T. 15 R. 4W
SE SW NE

Total Depth. 3416
Comm. 12-20-51 Comp. 1-5-52
Shot or Treated.
Contractor. E. K. Carey
Issued. 3-15-52

County Saline
KANSAS



CASING:

8 5/8" 315' cem. w/250 sx
4 1/2" 3414' cem. w/75 sx

Elevation. 1302 DF

Production. 386 BO & NW

Figures Indicate Bottom of Formations.

cellar	8
shale	35
sand	45
shale & shells	275
lime & shale	315
lime	410
lime & shale	805
lime	953
lime & shale	1125
shale & shells	1695
lime & shale	2240
lime	2550
lime & shale	2900
lime	3192
shale	3240
shale & lime	3300
shale	3324
lime	3346
shale	3414
lime	3416 RTD
Total Depth	

Tops:	
Miss.	2900
Kinderhook	3190
Hunton	3328
Maquoketa Shale	3344
Maquoketa Dolo.	3414