


OCT 27 2004

CONSERVATION DIVISION
WICHITA, KS



DRILL STEM TEST REPORT

Prepared For: **Pelican Hill Oil & Gas**

1401 N El Camino Real
Ste #207
San Clemente CA 92672

ATTN: Al Downing

6-15S-41W Greeley

Blasei #2-6

Start Date: 2004.08.21 @ 02:39:40

End Date: 2004.08.21 @ 11:40:25

Job Ticket #: 19632 DST #: 1

ARI 15-199-20316-00-00

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

Pelican Hill Oil & Gas

1401 NE Camino Real
Ste #207
San Clemente CA 92672
ATTN: Al Downing

Blasei #2-6

6-15S-41W Greeley

Job Ticket: 19632

DST#: 1

Test Start: 2004.08.21 @ 02:39:40

GENERAL INFORMATION:

Formation: **Morrow**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 04:44:40

Time Test Ended: 11:40:25

Interval: 4908.00 ft (KB) To 4969.00 ft (KB) (TVD)

Total Depth: 4969.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Good

Test Type: Conventional Bottom Hole

Tester: Rod Steinbrink

Unit No: 22

Reference Elevations: 3772.00 ft (KB)

3762.00 ft (CF)

KB to GR/CF: 10.00 ft

Serial #: 6798

Inside

Press@RunDepth: 644.77 psig @ 4909.00 ft (KB)

Start Date: 2004.08.21

End Date: 2004.08.21

Capacity: 7000.00 psig

Last Calib.: 1899.12.30

Start Time: 02:39:45

End Time: 11:40:25

Time On Btm: 2004.08.21 @ 04:38:25


Time Off Btm: 2004.08.21 @ 07:33:40

TEST COMMENT: IF; Strong blow off btm in 3 mins GTS @ 15 mins (TSTM)

IS; Blow never completely died

FF; Strong blow off btm in 2 mins

FS; Let bow go thru 2"



PRESSURE SUMMARY

Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2563.61	120.82	Initial Hydro-static
7	181.66	124.99	Open To Flow (1)
35	419.99	139.65	Shut-In(1)
82	1037.11	138.79	End Shut-In(1)
83	504.08	137.69	Open To Flow (2)
115	644.77	142.86	Shut-In(2)
174	1036.74	141.95	End Shut-In(2)
176	2301.59	141.55	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
2004.00	CGO 50%g 50%o	22.85

Gas Rates

	Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Pelican Hill Oil & Gas

Blasei #2-6

1401 NE Camino Real

6-15S-41W Greeley

Ste #207

Job Ticket: 19632

DST#: 1

San Clemente CA 92672

Test Start: 2004.08.21 @ 02:39:40

ATTN: Al Downing

Tool Information

Drill Pipe:	Length:	4324.00 ft	Diameter:	3.80 inches	Volume:	60.65 bbl	Tool Weight:	2500.00 lb
Heavy Wt. Pipe:	Length:	0.00 ft	Diameter:	0.00 inches	Volume:	0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length:	578.00 ft	Diameter:	2.25 inches	Volume:	2.84 bbl	Weight to Pull Loose:	110000.0 lb
					Total Volume:	63.49 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:		20.00 ft					String Weight: Initial	86000.00 lb
Depth to Top Packer:		4908.00 ft					Final	100000.0 lb
Depth to Bottom Packer:		ft						
Interval between Packers:		62.00 ft						
Tool Length:		88.00 ft						
Number of Packers:		2	Diameter:	6.75 inches				

Tool Comments:

Tool Description

Length (ft) Serial No. Position Depth (ft) Accum. Lengths

Shut In Tool	5.00			4887.00		
Hydraulic tool	5.00			4892.00		
Jars	5.00			4897.00		
Safety Joint	2.00			4899.00		
Packer	5.00			4904.00	26.00	Bottom Of Top Packer
Packer	4.00			4908.00		
Stubb	1.00			4909.00		
Recorder	0.00	6798	Inside	4909.00		
Perforations	23.00			4932.00		
Change Over Sub	1.00			4933.00		
Anchor	31.00			4964.00		
Change Over Sub	1.00			4965.00		
Recorder	0.00	13309	Outside	4965.00		
Bullnose	5.00			4970.00	62.00	Bottom Packers & Anchor

Total Tool Length: 88.00



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

FLUID SUMMARY

Pelican Hill Oil & Gas

Blasei #2-6

1401 N El Camino Real
Ste #207
San Clemente CA 92672
ATTN: Al Downing

6-15S-41W Greeley

Job Ticket: 19632

DST#: 1

Test Start: 2004.08.21 @ 02:39:40

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

38.4 deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 57.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.19 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 3000.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
2004.00	OGO 50%g 50%o	22.846

Total Length: 2004.00 ft

Total Volume: 22.846 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

DST Test Number: 1

6-15S-41W Greeley

Inside Pelican Hill Oil & Gas

Serial #: 6798

Pressure vs. Time

