

28-15-42W

Daily Drilling Reports

Trans-Western Krautkramer #1-28
SWSWSW Sec 28, T15S, 42W
Wallace County, Kansas
Projected TD: 5300'
Elevation 3875' KB (5' AGL)
API# 15-199-20,082

- 4-17-86 MIRU Murfin Rig 20 & spud 12¼" surface hole @ 7:15 PM 4-16-86. Drilling @ 172'. Down 10½ hrs repairing draw-works
- 4-18-86 Depth 1560', cut 1388', drlg in sand & shale. Drlg 12¼" hole to 386' & ran 9 jts (378.54') 8-5/8", 24# csg. Landed @ 386' & cmt by Allied w/100 sx lite + 110 sx common (210 sx total) w/3% CaCl₂. Plug down @ 1:15 PM 4-17-86. WOC 8 hrs & drld out w/Bit #1 7-7/8" HTC J2 retip. Lost circ 1 hr @ 1468'. Survey 1/8° @ 386', 1-1/8° @ 1100'.
- 4-19-86 Depth 2745', cut 1185', drlg in shale below salt. MW 9.4, Vis 28, Surveys: 1½° @ 1783', 1° @ 2326. Bit #1 out @ 1783', cut 1397' in 10½ hrs. Bit #2 HTC J22 w/3-12's. Lost circ ½ hr @ 1764'.
- 4-20-86 Depth 3645', cut 900', drlg in lime & shale. MW 9.3, Vis 27. Stone Corral anhydrite 2762-86.
- 4-21-86 Depth 4135', cut 490', drlg in Heebner shale. MW 9.2, Vis 27, LCM 1#, Lost circ 3/4 hr @ 3846'. Down 4 hrs pump repair & LD 1 jt DP.
- 4-22-86 Depth 4665', cut 530', drlg in lime & shale below Marmaton. MW 8.9, vis 39, WL 14, LCM 2½#, lost circ ¼ hr @ 4213' (upper Lansing). 4 drlg breaks w/no shows at: 4314-4321, 4422-4440, 4525-32, 4560-4564. Tops: Stone Corral - 2761', Lansing - 4178', Marmaton - 4636'.
- 4-23-86 Depth 5020', cut 355', drlg in Atoka. MW 9.2, Vis 47, WL 14, Cl 9,000, LCM 2#.
- 4-24-86 Depth 5302'. Td in Mississippian. MW 9.2, Vis 56, WL 12, Cl 10,000, Circ cond 1 hr, made 10 stand short trip. Circ 1 hr and strap OOH. Rigging up Great Guns WL to run primary logs.
- 4-25-86 Depth 5302'. Ran DIL FDC-CNL & Sonic logs. Plug in accord w/instructions from state inspector as follows:
 - 30 sx - 278'
 - 100 sx - 1825' w/celloflake
 - 50 sx - 420'
 Mousehole-15 sx
 Rathole - 15 sx

 Plug and abandon @ 11 PM @ 4-24-86. Final Report.

NOV 3 1986