

KANEX OIL, INC.
4121 WEST 83RD STREET
PRAIRIE VILLAGE, KANSAS 66208

JOHN I. WILLHAUCK, JR.
President

COMPLETION REPORT

COMANCHE #2
NW NW SE
SECTION 32, TOWNSHIP 15S, RANGE 8W
ELLSWORTH COUNTY, KANSAS

KB 1600
GL 1595

TUESDAY, MAY 4, 1982: Moved in Stevens double drum and rigged up.


Electra ran correlation log and perforated the Lecompton section of the Topeka 20 holes 2297 ft. to 2307 ft. (-698 to -708).

Ran 6 ft. perforated mud anchor, seating nipple and new 2" tubing. Seating nipple at top of perfs.

Halliburton acidized down tubing with 2000 gal 28% with 5 gal. HC-2 and 1000 gal. 15% NE with 5 gal. HC-2. 5 gal. HOWCO Suds in displacement water. Well broke at 400# and treated 4 BPM @ 750#. Instant 100#.

Lay Halliburton iron to pit and flow back. Well cleans up. Flow for 30 minutes. Shut in.

8:00 p.m.: 550# on well.


John I. Willhauck, Jr.

5/13/82