

BRG PETROLEUM, INC.

PRODUCTION REPORT:

Pickens #1

12-19-90 BRG took over operations. Reconnect electricity. Start well pumping. 24 hrs 5 B0 + 100 BW. Had 10% oil cut at wellhead this am. Had to shut well in and wait on repairs to SW pump.

Pickens #1/Kihn SWD

01-07-91 Pickens shut down due to problems with SWD pump. RU pump truck with gear pump on Kihn SWD. Took 4 BW to load tbg. Press to 200# and still climbing at 1/2 BPM. Well on slight vac in 6 min. Shut down.

Kihn SWD

01/08/91 Well standing on 24# vac. RU Howco. Pump 750 gal 15% HCL acid down tbg on 10# vac. Flush w/ 20 BW on 10". Taking wtr at rate of 20 BWPM. Shut in. Had 29# vac. Will reconnect to SW tank today.  
DWC: \$600

Pickens #1

01/08/91 Start well back up after repairing SWD.

01-09-91 21 hrs pump 23 B0 + 60 BW. Hook up to SWD well today.

01-10-91 22 hrs pump 15 B0. No gauge on wtr. Disposal well taking wtr on 23" vac.

01-11-91 24 hrs pump 13 B0 + approx 20 BW - 21" vac on SWD. Had to open a little.

01-12-91 24 hrs pump 13 B0 + approx 20 BW - 21" vac on SWD.

01-13-91 24 hrs pump 13 B0 + approx 20 BW - 23" vac on SWD.

01-14-91 26 hrs pump 15 B0 + approx 20 BW - 17" vac on SWD.

02-13-91 24 hrs pump 5 B0 + 62 BW. Installing SW pump.

02-14-91 24 hrs pump 5 B0. Installing SW pump.

02-15-91 Pump 5 B0 + 50 BW.

02-16-91 Pump 4 B0 + 50 BW.

02-17-91 Pump 4 B0 + 50 BW.

02-18-91 Pump 5 B0 + 50 BW.

02-20-91 Pumping 4-5 BOPD + 40-50 BWPD. Started SWD pump. Taking wtr at 10-15 psi.