

State Kansas County Rush (WXOI)Sec. 1 Twp. 16 Rng. 20W Elev. 2114Company Darby & RothwellWell No. 1 Name WeitzollLocation SW SW NW

Feet from lines: N. S. E. W.

Spud 3-19-17 Completed 4-23-17T. D. 3690 Casing 5" 3678

Comp. Perf.

Pay 3678-90 in Pre-Camb.I. P. Phy. pot. 19 1/2 OPD, tr. wtr.

Choke T. P. C. P.

G. O. R. 3678
2114
1524 Grvty.

| DATE | REMARKS |
|---------|--|
| 4-23-17 | Top. 3105, Heeb. 3343, Lans. 3384, B-KG 3609, Pre-Camb. 3678. |
| | Slt. str. 3389-92, 3399-3401, 3405-08 NS, ool. slt. vug. |

DATE

REMARKS

Little FO 3402-12, on 3/13.

DST 3403-13, open 30 min.,

gd. blow, rec. 120' O & GCM,

30' oil, no wtr.,

Sft. 3538-42, slt. por. & stn.

Sft. 3568-72, NS,

SSO 3678-90, DST 3678-90, open

30 min., rec. 510' middy oil,

Flw out drill pipe, oil blank,

Grav. Est. 35.

DP 3690 TD, FU 1200' Oil/30

1600' oil/45, 2000' oil/1 1/2 hrs.

Swb/50 BO/5, Swb/8 BOPH/2

Est. Grav. 40.

P/143.28 IP/24, approx. 12%

wtr.

Phy. pot. 19 1/4 BOPD, gr. out 11 1/2

wtr.

Grav. 35 corr.

COMPLETE

6/16/30