

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

20-16-10W

Company - H. V. ELWELL
Farm - Lanzi

No. 2

SEC. 20 T. 16 R. 10W
NE NW SE

Total Depth. 3332'

Comm. 2-23-47


Comp. 4-3-47

Shot or Treated.

Contractor. Three Way Drilling Co.

Issued. 8-23-47

County. Ellsworth
KANSAS



Elevation. 1850 feet

Production. 25 BO

CASING:

10" 370' Com.

7" OD 3304' Com.

Figures Indicate Bottom of Formations.

shale, sand & shells	310
shale & shells	465
red rock & shale	715
anhydrite	750
red bed	790
shale & shells	1080
salt & shells	1265
shale & shells	1380
lime brkn	1395
lime	1430
anhydrite lime	1440
shale & shells	1490
lime	1520
lime brkn	1570
shale & shells	1610
lime & shale	1680
lime brkn	1725
lime	1750
lime & shale	1785
lime	1880
red rock & shale	1886
lime	1930
lime & shale	2195
lime	2230
shale & shells	2340
lime	2344
lime & shale	2616
lime brkn	2665
lime	2890
shale & lime	2930
shale	2991
lime	3132
lime & shale	3165
lime T.D. (rot.)	3305
lime	3332
Total Depth (Cable)	

Tops:

Lansing K. C.	3000
Base K. C. Lime	3264
Cherty Shaly,	
conglomerate	3298
Arbuckle dolomite	3302
3302-05' Brwn, med	
xlyn, dolomite w/no	
oil stain or odor.	