

20-16-10W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - LION OIL CO.
Farm Valenta No. 4

SEC. 20 T. 16 R. 10 W
NE NW NW

Total Depth. 3386'
Comm. 11-20-45 Comp. 12-13-45
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 4-20-46

County. Ellsworth
KANSAS



Elevation. 1884

Production. Dry

CASING:

8 5/8" 365' Cem.
5 1/2" 3356' Cem.

Figures Indicate Bottom of Formations.

shale & shells	675
anhydrite	685
shale & shells	990
shale, shells & salt	1250
shale & salt	1350
shale & shells	1800
lime & shale	1860
lime lgt hrd	1995
lime hrd	2080
lime	2160
lime lgt med	2197
lime lgt hrd	2220
lime & shale	2275
lime & shale brks	2450
lime & shale	2535
lime & shale brks	2590
lime lgt hrd	2935
lime & shale	3025
lime lgt hrd	3335
lime lgt med	3350
lime lgt hrd	3356
lime hrd	3360

Total Depth w/Rot. 3386
lime Arbuckle 3386
Total Depth.

Top of Arbuckle 3356'