

4-16-10W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HENDERSON OIL CO.
Farm- Borecky No. 3

SEC. 4 T. 16 R. 10W
NW SE NE

Total Depth. 3366
Comm. 7-24-55 Comp. 8-1-55

County Ellsworth
KANSAS

Shot or Treated.
Contractor. The Carl Todd Drilling Co.
issued. 10-15-55



8 5/8 @ CASING: 355' w/ 225 sx cmt.
5 1/2 @ 3359' w/ 75 sx cmt.

Elevation. 1822 KB

Production. 180 BOPD

Figures Indicate Bottom of Formations.

clay & lime	30
lime & shale	290
sand	305
shale & shells	355
sand & iron	430
shale, sand & iron	480
red bed & iron	590
anhydrite	615
shale & red bed	1125
shale	1350
shale & lime	1660
sand	1695
shale	1740
lime & shale	2055
shale	2565
shale & lime	2685
lime	2805
lime & shale	2915
shale	2955
lime	3310
lime & shale	3355
sand & lime	3359
Arbuckle	3366
Total Depth	

TOPS:

Heebner	2852
Brown lime	2954
Lansing	2973
Base KC	3255
Conglomerate	3287
Arbuckle	3358

DST #1: 3358-66, open 1 hr, rec. 600'
oil, IFP 0#, FFP 240#, BHP 1060#