

4-16-10W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GRANT OIL COMPANY
Farm- E. Sebesta No. 1

SEC. 4 T. 16 R. 10W
NW NW SW

Total Depth. 3287'
Comm. 3-4-57 Comp. 3-24-57
Shot or Treated.
Contractor. Birmingham-Bartlett Drilg. Co.
Issued. 5-23-59

County Ellsworth
KANSAS



CASING:

Elevation. 1795' RB

8 5/8" @ 288' cen. w/175 sx.
5 1/2" @ 3286' cen. w/100 sx.

Production. 25 BOPD

Figures indicate Bottom of Formations.

sand, clay & shale	288
shale, shells & sand	350
red bed and shells	592
anhydrite	622
shale & shells	1250
lime & shale	1765
shale & shells	2035
shale	2295
shale & shells	2485
lime & shale	2705
lime	2818
lime & shale	2935
lime	3264
shale & sand	3272
shale	3285
lime	3287 RTD
Total Depth	

TOPS: SCOUT

Anhydrite	592
Topeka	2525
Haebner	2820
Brown Lime	2822
Kansas City	2938
Simpson	3258
Arbuckle	3285