

4-16-10W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company. MAGNOLIA PETRO. CO.
Farm. John Skalicky No. 2

SEC. 4 T. 16 R. 10W
NE SW SW SW
600' fr W1 & 410' fr S1 of SW $\frac{1}{4}$

Total Depth. 3858' K.B.

Comm. 9-12-48

Comp. 10-21-48


Shot or Treated.

Contractor. Quaker Drilg. Co.

Issued. 1-8-49

County. Ellsworth

KANSAS



Elevation. 1760 *ft.*
1759 *ft.*

Production. Salt wtr Disposal Well

CASING:

10-3/4" 352' Cem. W/175 Sx.
7" 3040' Cem. W/ 300 Sx.

Figures Indicate Bottom of Formations.

lime, shells & shale	205
sand	300
shale, lime & shells	352
shale & lime shells	365
shale & red bed	555
anhydrite	675
shale & shells	1250
lime & shale	1340
sdv lime & pyrites	
of iron	1456
lime & shale	1610
lime sdv	1635
lime & shale	1700
sdv lime & shale	1800
shale & lime	2580
lime	2640
lime & shale	3379
lime, shale & chert	3399
lime cherty	3574
lime	3591
lime sdv	3594
lime gy	3615
lime	3621
lime gy	3672
lime	3694
lime sdv	3778
lime	3800
lime sdv	3809
lime wh sdv	3811
drk sand lime & shale	3819
lime	3821
sand, lime & shale	3824
lime brwn hrd	3834
lime	3835
lime sdv	3848
lime & shale	3850
lime brwn	3858 K. B.
Total Depth	

Tops:

Simpson 3253

Arbuckle 3269