

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted
5-16-10 W
SEC. 5 T. 16 R. 10W.
CEL SW SW
990' FWL 660' FSL S $\frac{1}{2}$ SW $\frac{1}{2}$

MAGNOLIA PETROLEUM CO.
J. Haska No. 3

Total Depth. 3267 SLM
Comm. 11-15-40 Comp. 12-6-40
Shot or Treated.
Contractor.
Issued. 1-18-41

County Ellsworth.



CASING.

103/4" 361' Cemented.
5 1/2" 3260' Cemented.

Elevation.

Production. Pot. 834 B.

Figures Indicate Bottom of Formations. 28% wtr. Echometer.

cellar	10
shale and shells	140
sand	180
shale and lime	361
shale and shells	980
shale and salt	1410
lime and shale	1640
sand	1665
shale	1670
shale and lime	1720
lime	1950
shale and lime	2545
shale and shells	2740
lime	2785
lime and shale	2940
lime	3110
lime and shale	3260

Very small show oil 3258-3260
Standardized
Drilled plug and cleaned out.
Arbuckle lime 3267 SLM Total Depth.
Bailed 5 gal oil per hr. No water.
Acidized with 1000 gal thru 2 1/2" Tubing.
Used 79 bbls oil Maximum pressure 1350#.

Swabbed 23 bbls oil per hr, 400' off
bottom 1% to 3% water for 7 hours.

Swabbed 26 bbls oil per hr. 200' off bottom
1% to 3% water for 7 hours.

Tops -

Lansing	2953 DF
Ordovician Cong.	3253 DF
Arbuckle	3256 DF