

5-16-10W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SOHIO PETROLEUM COMPANY

SEC. 5 T. 16 R. 10^W
LOC. SE NW SE

FARM Haska NO. 3

TOTAL DEPTH 3305

COMM. 12-6-50

COMP. 12-17-50


SHOT OR TREATED

CONTRACTOR Penguin Petroleum, Inc.

ISSUED 1-27-51

COUNTY Ellsworth

KANSAS



CASING

8 5/8" 315' cem. w/200 sx

5 1/2" 3305' cem. w/100 sx

1838 Ind.
ELEVATION 1840 R.B.

PRODUCTION DD Pot. 3000 Bbls.
oil per day & No wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

rock	25
blue shale	150
shale	285
lime	315
blue shale	375
shale & shells	610
redbed	645
Anhydrite	670
shale	690
shale & shells	1390
lime	1640
shale	1700
lime	1790
shale	1815
shale & lime	2035
shale	2620
lime	2900
shale	2968
lime & shale	3015
lime	3080
sandy lime	3100
lime	3305
Total depth	

Tops:

Heebner	2866
Brown lime	2967
Lansing	2987
Arbuckle	3302

Drill Stem Test @ 3100' , recovery
90' muddy water B.H.P. 950#.